


THIS DOCUMENT BELONGS TO REPSOL. IT CAN NOT BE COPIED, REPRODUCED AND/OR USED WITHOUT PREVIOUS AUTHORIZATION OF REPSOL. COMPUTERIZED DRAWING (HANDWRITING STRICTLY FORBIDDEN).

EXTR. DATE: 16-12-2023 13:09:32

STREAM NO.:4552 STREAM REV. NO. : 10 REV. CAUSE ID: 23



BILL OF MATERIAL					
PT NO	COMPONENT DESCRIPTION	N.S. (IN)	ITEM CODE	QTY	HOLD STATUS
PIPE					
1	PIPE - A106-B PE SMLS T01AC03Z02 S-XS <PIPA010A11XS> (L-6679)	1	I132793	2.7 M	
2	PIPE - A106-B PE SMLS T01AC03Z02 S-XS <PIPA010A13/4XS> (L-6679)	3/4	I132785	0.1 M	
FITTINGS					
3	TEE ASME B16.11 3000# A105N SWE SWE - R11FNC441101 NREQD <TESA300LBK11/2> (L-179)	1.1/2X1.1/2	I1651302	1	
4	ECCENTRIC SWAGE MSS SP-95 - A105N PE PE SMLS SCH1-XS SCH2-XS R22FQC44ZZ01 <ESWA010AR13161216> (L-ESW31)	1.1/2X1	I62946435	2	
5	REDUCING 45 LATERAL ASME B16.11/AA 3000# A105N SWE SWE - R18RNC441101 Undefined <LR4A300LB1211> (L-LR403)	1X3/4	I63782626	1	
6	REDUCING 45 LATERAL ASME B16.11/AA 3000# A105N SWE SWE - R18RNC441101 Undefined <LR4A300LB1210> (L-LR403)	1X1/2	I63782625	1	
7	COUPLING ASME B16.11 3000# A105N SWE SWE - R01FNC441101 NREQD <FCPA300LBK1> (L-180)	1	I1651677	2	
8	NIPPLE - - A106-B PE MTE SMLS LENGTH 100mm R03AQCO3ZW04 S-XS <NTOA010E1121624> (L-7888)	1	I2221194	1	
9	CAP ASME B16.11 3000# A105N FTE NREQD - R41FNC442001 NREQD <CATA300KBK1> (L-79)	1	I1651687	1	
FLANGES					
10	SW FLANGE ASME B16.5 150# A105N RFFE SWE 125 - 250 AARH F02CDC44B105 S-XS <SWFA300R151XS> (L-295)	1	I5378343	2	
11	SW FLANGE ASME B16.5 150# A105N RFFE SWE 125 - 250 AARH F02CDC44B105 S-XS <SWFA300R153/4XS> (L-295)	3/4	I5378342	1	
12	BLIND FLANGE ASME B16.5 150# A105N RFFE NREQD 125 - 250 AARH F10CDC44B005 <BLFA300R153/4> (L-140)	3/4	I1652356	1	
GASKETS					
13	SPIRAL WOUND GASKET ASME B16.20 150# RFFE 304/PTFE CARBON STEEL SS 304 ASME B16.5 G03GDB11G12 <SPAQ505R1EA1> (L-SPA04)	1	I2230476	2	
14	SPIRAL WOUND GASKET ASME B16.20 150# RFFE 304/PTFE CARBON STEEL SS 304 ASME B16.5 G03GDB11G12 <SPAQ505R1EA3/4> (L-SPA04)	3/4	I2230475	2	
BOLTS					
15	STUD BOLTS&NUTS ASME B18.31.2/ B18.2.2 A193-B7/A194-2H INCH SIZE I01OB0301 <SB2R51G1/221/2> - 2 NUTS PER BOLT - 65 mm Length	1/2	I53437190	16	
VALVES / IN-LINE ITEMS					
16	BALL VALVE API 608 150# A216-WCB RFFE 316/R-PTFE, GF B7/2H 125 - 250 AARH 2PSB-FULL BORE FLOATING BALL OHW ASME B16.5 V04JDC29BZZG NREQD <N/A> (N/A)	1	I10013687	1	
17	BALL VALVE API 608 150# A216-WCB RFFE 316/R-PTFE, GF B7/2H 125 - 250 AARH 2PSB-FULL BORE FLOATING BALL OHW ASME B16.5 V04JDC29BZZG NREQD <N/A> (N/A)	3/4	I10013686	1	

REMARKS FOR MECHANICAL SUBCONTRACTOR:

- 1) LINES 1.1/2" AND SMALLER SHALL BE SUPPORTED IN FIELD IF NOT OTHERWISE INDICATED.
2) ALL DIMENSION AND PROPER CONFIGURATION FOR LINES NPS 1.1/2" AND SMALLER SHALL BE CHECKED IN FIELD BEFORE CONSTRUCTION.
3) FOR THE COMPONENTS MARKED AS FIELD WELDED WITH THIS SYMBOL ✕ , ONE WELD FOR ADJUSTMENT OF IN LINE COMPONENT MUST BE LEFT
4) FOR EXTRA PIPE LENGTH REFER TO 4274-LZ-PC-00000603.
5) GUSSETING TO BE IMPLEMENTED BY MECHANICAL SUBCONTRACTOR AS PER 45-L-45-000-2-00-80004 / 4274-XH-SG-00000002.
6) CROSSING BETWEEN WELDS ON PIPELINE SHALL NOT BE ADMITTED.
7) IN CASE OF DISCREPANCIES BETWEEN DATA SHOWN ON ISO AND IN LINE LIST (AS APPLICABLE, DATA SHOWN IN LINE LIST GOVERN.
8) ACTUAL CUT LENGTH OF PIPE AND FIELD WELDS SHALL BE DEFINED BY MECHANICAL SUBCONTRACTOR (REF.TO 4274-LZ-PC-00000603).
9) WHERE EARTHING BONDING IS REQUIRED, MECHANICAL SUBCONTRACTOR TO PERFORM IT BASED ON DOC. 45-P-000-7-06-00902/ 4274 -NN-DW-00000002 AND ASSEMBLY NO FEA005 AND FE019.

SUPPORTS LEGEND:		☐ DENOTES PARTS LIST NO	PIPE SUPPORT	—	A=RESTING SUPPORT WHERE ☐ WITHOUT NUMBERING IS INDICATED, THIS MEANS THAT THERE IS A REST DIRECTLY ON STEEL STRUCTURE.	G=GUIDE	F=AXIAL STOP	B=ANCHOR	M=SPRING	S=TEFLON PAD
------------------	--	-------------------------	--------------	---	---	---------	--------------	----------	----------	--------------



							STRESS CALC. N°
							-
01	ISSUED FOR REFERENCE	16-DEC-23	M.YADAV	P.VAZE	G.PAGANONI		P & ID 19-A-19-000-1-01-00001 sheet 35
00	ISSUED FOR REFERENCE	07-JUL-23	U.CHAVAN	P.VAZE	G.PAGANONI		LINE LIST N° 19-L-19-000-2-00-80602
REV.	DESCRIPTION	DATE	DRW. BY	CHECK BY	APPR. BY	APPR. CLIENT	PIPE LAYOUT N° 19-L-19-000-2-00-86196 sheet 2

ISSUED FOR REFERENCE

Signature for construction is shown on Iso list of relevant CWA

ISOMETRIC DRAWING LINE

1-1/2"-CT-49A23-1C14

PIPE MATERIAL		NOTES: 1. FOR TECHNICAL DETAILS SEE LINE LIST. 2. FOR VENT, DRAIN OR INSTRUMENT CONNECTION DETAILS SEE 45-L-45-000-2-00-80102. 3. WELDING ACCORDING TO 45-L-45-000-2-00-80021. 4. PAINTING ACCORDING TO 45-A-45-000-1-00-20160. 5. CODE SHOWN IN BOM BETWEEN "<" & ">" DENOTES REPSOL UNICODE. "<N/A>" MEANS UNICODE IS "NOT AVAILABLE".				
CS						
HEAT TREATMENT (PWHIT)						
N						
PAINTING SCHEME (3)			CONTRACTOR:		CONTRACTOR DRAWING NUMBER:	PROJECT:
1					4274-XH-DL-2121CT49A23-2	4001008
PIPING CLASS						
IC14						
WELDING CLASS (4)		 LOW LINEAL DENSITY POLYETHYLENE (PEL) AND POLYPROPYLENE (PP) PLANTS FOR PROJECT - ALBA PROJECT				CLIENT / COMPLEX REPSOL POLYMEROS/ SINES INDUSTRIAL COMPLEX
E-2						
PED CATEGORY						
I						
INSULATION CODE / THK. (mm)		ANNEX 19	SPEC. L	DRAWING NUMBER 19-000-2-02-00001 sheet 2121CT49A23-2		REV. 01
N 0						