


THIS DOCUMENT BELONGS TO REPSOL. IT CAN NOT BE COPIED, REPRODUCED AND/OR USED WITHOUT  
PREVIOUS AUTHORIZATION OF REPSOL. COMPUTERIZED DRAWING (HANDWRITING STRICTLY FORBIDDEN).



EXTR. DATE: 12-12-2023 12:02:35

STREAM NO.:4300    STREAM REV. NO. : 10    REV. CAUSE ID: 23



BILL OF MATERIAL				
PT NO	COMPONENT DESCRIPTION	N.S. (IN)	ITEM CODE	HOLD STATUS
PIPE				
1	PIPE - A106-B PE SMLS T01AC03Z02 S-XS <PIPA010A13/4XS> (L-6679)	3/4	I132785	1.4 M
FITTINGS				
2	90 ELBOW ASME B16.11 3000# A105N SWE SWE - R31FNC441103 NREQD <90FA300LBK3/4> (L-178)	3/4	I1651298	4
FLANGES				
3	SW FLANGE ASME B16.5 150# A105N RFFE SWE 125 - 250 AARH F02CDC44B105 S-XS <SWFA300R153/4XS> (L-295).	3/4	I5378342	1

REMARKS FOR MECHANICAL SUBCONTRACTOR:							
1) LINES 1.1/2" AND SMALLER SHALL BE SUPPORTED IN FIELD IF NOT OTHERWISE INDICATED.							
2) ALL DIMENSION AND PROPER CONFIGURATION FOR LINES NPS 1.1/2" AND SMALLER SHALL BE CHECKED IN FIELD BEFORE CONSTRUCTION.							
3) FOR THE COMPONENTS MARKED AS FIELD WELDED WITH THIS SYMBOL ✕ , ONE WELD FOR ADJUSTMENT OF IN LINE COMPONENT MUST BE LEFT							
4) FOR EXTRA PIPE LENGTH REFER TO 4274-LZ-PC-00000603.							
5) GUSSETING TO BE IMPLEMENTED BY MECHANICAL SUBCONTRACTOR AS PER 45-L-45-000-2-00-80004 / 4274-XH-SG-00000002.							
6) CROSSING BETWEEN WELDS ON PIPELINE SHALL NOT BE ADMITTED.							
7) IN CASE OF DISCREPANCIES BETWEEN DATA SHOWN ON ISO AND IN LINE LIST (AS APPLICABLE, DATA SHOWN IN LINE LIST GOVERN.							
8) ACTUAL CUT LENGTH OF PIPE AND FIELD WELDS SHALL BE DEFINED BY MECHANICAL SUBCONTRACTOR (REF.TO 4274-LZ-PC-00000603).							
9) WHERE EARTHING BONDING IS REQUIRED, MECHANICAL SUBCONTRACTOR TO PERFORM IT BASED ON DOC. 45-P-000-7-06-00902/ 4274 -NN-DW-00000002 AND ASSEMBLY NO FEA005 AND FE019.							
SUPPORTS LEGEND:							
☐ DENOTES PARTS LIST NO		PIPE SUPPORT	—	A=RESTING SUPPORT	G=GUIDE	F=AXIAL STOP	B=ANCHOR
				WHERE ☐ WITHOUT NUMBERING IS INDICATED, THIS MEANS THAT THERE IS A REST DIRECTLY ON STEEL STRUCTURE.		M=SPRING	S=TEFLON PAD
							STRESS CALC. N°
01	ISSUED FOR REFERENCE						-
							P & ID
							19-A-19-000-1-01-00001 sheet 45
							LINE LIST N°
							19-L-19-000-2-00-80602
							PIPE LAYOUT N°
							19-L-19-000-2-00-86197 sheet 1
REV.	DESCRIPTION	DATE	DRW. BY	CHECK BY	APPR. BY	APPR. CLIENT	

ISSUED FOR REFERENCE	PIPE MATERIAL		NOTES: 1. FOR TECHNICAL DETAILS SEE LINE LIST. 2. FOR VENT, DRAIN OR INSTRUMENT CONNECTION DETAILS SEE 45-L-45-000-2-00-80102. 3. WELDING ACCORDING TO 45-L-45-000-2-00-80021. 4. PAINTING ACCORDING TO 45-A-45-000-1-00-20160. 5. CODE SHOWN IN BOM BETWEEN "<" & ">" DENOTES REPSOL UNICODE. ~N/A~ MEANS UNICODE IS "NOT AVAILABLE".							
	CS									
	HEAT TREATMENT (PWHT)									
	N									
Signature for construction is shown on Iso list of relevant CWA	PAINTING SCHEME (3)				CONTRACTOR DRAWING NUMBER:		PROJECT:			
	1				4274-XH-DL-2121FO40P01-2		4001008			
	PIPING CLASS									
	1C17									
TITLE	WELDING CLASS (4)		 LOW LINEAL DENSITY POLYETHYLENE (PEL) AND POLYPROPYLENE (PP) PLANTS FOR PROJECT - ALBA PROJECT				CLIENT / COMPLEX REPSOL POLYMEROS/ SINES INDUSTRIAL COMPLEX			
ISOMETRIC DRAWING LINE	E									
	PED CATEGORY									
	Art 4.3									
3/4"-FO-40P01-1C17	INSULATION CODE / THK. (mm)		ANNEX 19		SPEC. L		DRAWING NUMBER 19-000-2-02-00001 sheet 2121FO40P01-2		REV. 01	
	N 0									