


THIS DOCUMENT BELONGS TO REPSOL. IT CAN NOT BE COPIED, REPRODUCED AND/OR USED WITHOUT  
PREVIOUS AUTHORIZATION OF REPSOL. COMPUTERIZED DRAWING (HANDWRITING STRICTLY FORBIDDEN).

EXTR. DATE: 06-07-2023 09:24:29





STREAM NO.:4404

REV. CAUSE ID: 4



REMARKS FOR MECHANICAL SUBCONTRACTOR:

- 1) LINES 1.1/2" AND SMALLER SHALL BE SUPPORTED IN FIELD IF NOT OTHERWISE INDICATED.
- 2) ALL DIMENSION AND PROPER CONFIGURATION FOR LINES NPS 1.1/2" AND SMALLER SHALL BE CHECKED IN FIELD BEFORE CONSTRUCTION.
- 3) FOR THE COMPONENTS MARKED AS FIELD WELDED WITH THIS SYMBOL , ONE WELD FOR ADJUSTMENT OF IN LINE COMPONENT MUST BE LEFT
- 4) FOR EXTRA PIPE LENGTH REFER TO 4274-LZ-PC-00000603.
- 5) GUSSETING TO BE IMPLEMENTED BY MECHANICAL SUBCONTRACTOR AS PER 45-L-45-000-2-00-80004 / 4274-XH-SG-00000002.
- 6) CROSSING BETWEEN WELDS ON PIPELINE SHALL NOT BE ADMITTED.
- 7) IN CASE OF DISCREPANCIES BETWEEN DATA SHOWN ON ISO AND IN LINE LIST (AS APPLICABLE, DATA SHOWN IN LINE LIST GOVERN.
- 8) ACTUAL CUT LENGTH OF PIPE AND FIELD WELDS SHALL BE DEFINED BY MECHANICAL SUBCONTRACTOR (REF.TO 4274-LZ-PC-00000603).
- 9) WHERE EARTHING BONDING IS REQUIRED, MECHANICAL SUBCONTRACTOR TO PERFORM IT BASED ON DOC. 45-P-000-7-06-00902/ 4274 -NN-DW-00000002 AND ASSEMBLY NO FEA005 AND FE019.

**SUPPORTS LEGEND:**  DENOTES PARTS LIST NO  PIPE SUPPORT  A=RESTING SUPPORT G=GUIDE F=AXIAL STOP B=ANCHOR M=SPRING S=TEFLON PAD WHERE  WITHOUT NUMBERING IS INDICATED, THIS MEANS THAT THERE IS A REST DIRECTLY ON STEEL STRUCTURE.

							STRESS CALC. N°
01	ISSUED FOR CONSTRUCTION	06-JUL-23	M.YADAV	P.VAZE	G.PAGANONI		P & ID 19-A-19-000-1-01-00001 sheet 49
00	ISSUED FOR CONSTRUCTION	16-DEC-22	U.CHAVAN	P.VAZE	G.PAGANONI		LINE LIST N° 19-L-19-000-2-00-80602
REV.	DESCRIPTION	DATE	DRW. BY	CHECK BY	APPR. BY	APPR. CLIENT	PIPE LAYOUT N° 19-L-19-000-2-00-86197 sheet 6

APPROVED FOR  
CONSTRUCTION

Signature for construction is shown  
on Iso list of relevant CWA

TITLE  
**ISOMETRIC DRAWING  
LINE**

3"-VA-40U07-1C2

BILL OF MATERIAL

PT NO	COMPONENT DESCRIPTION	N.S. (IN)	ITEM CODE	QTY	HOLD STATUS
<b>PIPE</b>					
1	PIPE - A106-B BE SMLS T01AC03V02 S-STD <PIPA010B13STD> (L-7806).	3	I117921	2.2 M	
<b>FITTINGS</b>					
2	ECCENTRIC REDUCER ASME B16.9 A234-WPB BE SMLS C22DC04V01 S-STD S-STD <EREA200F315151415> (L-7959)	3X2	I128082	1	
3	90 LR ELBOW ASME B16.9 A234-WPB BE SMLS C01DC04V01 S-STD <90LA200F33STD> (L-7955).	3	I128599	2	
<b>FLANGES</b>					
4	WN FLANGE ASME B16.5 150# A105N RFFE BE 125 - 250 AARH F01CDC44BV05 S-STD <WNFA300R152STD> (L-149)	2	I5355795	1	
<b>PIPE SUPPORTS</b>					
5	GUIDE AND STOP HORIZ VERT SUPPORT-N1B1	3	40	1	
6	STAKES SUPPORTS ST05 HEA140	3	40	1	
<b>GASKETS</b>					
7	SPIRAL WOUND GASKET ASME B16.20 150# RFTBE 304/GRAFOIL CARBON STEEL SS 304 ASME B16.5 G03GDP1IS12 <N/A> (N/A)	2	I63508906	1	
<b>BOLTS</b>					
8	STUD BOLTS&NUTS ASME B18.31.2/ B18.2.2 A193-B7/A194-2H INCH SIZE I01OB0301 <SB2R51G5/831/2> - 2 NUTS PER BOLT - 85 mm Length	5/8	I53437429	4	

PIPE MATERIAL

CS

HEAT TREATMENT (PWHT)

N

PAINTING SCHEME (3)

1

PIPING CLASS

1C2

WELDING CLASS (4)

E

PED CATEGORY

Art 4.3

INSULATION CODE / THK. (mm)

N

0

- NOTES: 1. FOR TECHNICAL DETAILS SEE LINE LIST.  
2. FOR VENT, DRAIN OR INSTRUMENT CONNECTION DETAILS SEE 45-L-45-000-2-00-80102.  
3. WELDING ACCORDING TO 45-L-45-000-2-00-80021.  
4. PAINTING ACCORDING TO 45-A-45-000-1-00-20160.  
5. CODE SHOWN IN BOM BETWEEN "<" & ">" DENOTES REPSOL UNICODE. "<N/A>" MEANS UNICODE IS "NOT AVAILABLE".



LOW LINEAL DENSITY POLYETHYLENE (PEL)  
AND POLYPROPYLENE (PP) PLANTS  
FOR PROJECT - ALBA PROJECT

CLIENT / COMPLEX  
REPSOL POLYMEROS/  
SINES INDUSTRIAL COMPLEX

ANNEX  
19

SPEC.  
L

DRAWING NUMBER  
19-000-2-02-00001 sheet 2121VA40U07-1

REV.  
**01**