








EXTR. DATE: 16-02-2024 18:50:45      STREAM NO.: 43      STREAM REV. NO.: 10      REV. CAUSE ID: 23



BILL OF MATERIAL					
PT NO	COMPONENT DESCRIPTION	N.S. (IN)	ITEM CODE	QTY	HOLD STATUS
PIPE					
1	PIPE - A106-B PE SMLS T01AC03Z02 S-XS <PIPA010A11XS> (L-6679)	1	I132793	5.9 M	
2	PIPE - A106-B PE SMLS T01AC03Z02 S-XS <PIPA010A13/4XS> (L-6679)	3/4	I132785	4.6 M	
FITTINGS					
3	REDUCING TEE ASME B16.11 3000# A105N SWE SWE - R12FNC441101 NREQD <RTEA300KBK13/4> (L-RTE15)	1X3/4	I1651305	2	
4	ECCENTRIC SWAGE MSS SP-95 - A105N PE PE SMLS SCH1-XS SCH2-XS R22FQC44ZZ01 <ESWA010AR12161116> (L-ESW31)	1X3/4	I63782597	1	
5	90 ELBOW ASME B16.11 3000# A105N SWE SWE - R31FNC441103 NREQD <90FA300LBK1> (L-178)	1	I1651296	2	
6	COUPLING ASME B16.11 3000# A105N SWE SWE - R01FNC441101 NREQD <FCPA300LBK3/4> (L-180)	3/4	I1651676	1	
7	45 ELBOW ASME B16.11 3000# A105N SWE SWE - R32FNC441101 NREQD <45FA300LBK3/4> (L-184)	3/4	I1651294	2	
8	90 ELBOW ASME B16.11 3000# A105N SWE SWE - R31FNC441103 NREQD <90FA300LBK3/4> (L-178)	3/4	I1651298	1	

<div>MARKS FOR MECHANICAL SUBCONTRACTOR:</div> <div>1) LINES 1.1/2" AND SMALLER SHALL BE SUPPORTED IN FIELD IF NOT OTHERWISE INDICATED.</div> <div>2) ALL DIMENSION AND PROPER CONFIGURATION FOR LINES NPS 1.1/2" AND SMALLER SHALL BE CHECKED IN FIELD BEFORE CONSTRUCTION.</div> <div>3) FOR THE COMPONENTS MARKED AS FIELD WELDED WITH THIS SYMBOL  , ONE WELD FOR ADJUSTMENT OF IN LINE COMPONENT MUST BE LEFT</div> <div>4) FOR EXTRA PIPE LENGTH REFER TO 4274-LZ-PC-00000603.</div> <div>5) GUSSETING TO BE IMPLEMENTED BY MECHANICAL SUBCONTRACTOR AS PER 45-L-45-000-2-00-80004 / 4274-XH-SG-00000002.</div> <div>6) CROSSING BETWEEN WELDS ON PIPELINE SHALL NOT BE ADMITTED.</div> <div>7) IN CASE OF DISCREPANCIES BETWEEN DATA SHOWN ON ISO AND IN LINE LIST (AS APPLICABLE, DATA SHOWN IN LINE LIST GOVERN.</div> <div>8) ACTUAL CUT LENGTH OF PIPE AND FIELD WELDS SHALL BE DEFINED BY MECHANICAL SUBCONTRACTOR (REF. TO 4274-LZ-PC-00000603).</div> <div>9) WHERE EARTHING BONDING IS REQUIRED, MECHANICAL SUBCONTRACTOR TO PERFORM IT BASED ON DOC. 45-P-000-7-06-00902/ 4274-NN-DW-00000002 AND ASSEMBLY NO FEA005 AND FEB19.</div>							<div>ISSUED FOR REFERENCE</div> <div>Signature for construction is shown on Iso list of relevant CWA</div>		<div>PIPE MATERIAL</div> <div>CS</div> <div>HEAT TREATMENT (PWHT)</div> <div>N</div>		<div>NOTES:</div> <div>1. FOR TECHNICAL DETAILS SEE LINE LIST.</div> <div>2. FOR VENT, DRAIN OR INSTRUMENT CONNECTION DETAILS SEE 45-L-45-000-2-00-80102.</div> <div>3. WELDING ACCORDING TO 45-L-45-000-2-00-80021.</div> <div>4. PAINTING ACCORDING TO 45-A-45-000-1-00-20160.</div> <div>5. CODE SHOWN IN BOM BETWEEN "&lt;" &amp; "&gt;" DENOTES REPSOL UNICODE. "&lt;N/A&gt;" MEANS UNICODE IS "NOT AVAILABLE".</div>									
<div>SUPPORTS LEGEND:</div> <div> DENOTES PARTS LIST NO PIPE SUPPORT  A=RESTING SUPPORT G=GUIDE F=AXIAL STOP B=ANCHOR M=SPRING S=TEFLON PAD WHERE  WITHOUT NUMBERING IS INDICATED, THIS MEANS THAT THERE IS A REST DIRECTLY ON STEEL STRUCTURE.</div>							<div>Signature for construction is shown on Iso list of relevant CWA</div>		<div>PAINTING SCHEME (3)</div> <div>1</div> <div>PIPING CLASS</div> <div>B-1</div>		<div>CONTRACTOR:</div> <div></div>		<div>CONTRACTOR DRAWING NUMBER:</div> <div>4274-XH-DL-2121IW91N28-1</div>		<div>PROJECT:</div> <div>4001008</div>					
							STRESS CALC. N° -	TITLE		<div>WELDING CLASS (4)</div> <div>E</div> <div>PED CATEGORY</div> <div>Art 4.3</div>		<div>LOW LINEAL DENSITY POLYETHYLENE (PEL) AND POLYPROPYLENE (PP) PLANTS</div> <div></div> <div>CLIENT / COMPLEX REPSOL POLYMERS/ SINES INDUSTRIAL COMPLEX</div>								
01	ISSUED FOR REFERENCE		16-FEB-24	M.YADAV	P.VAZE	G.PAGANONI	P & ID 19-A-19-000-1-01-00001 sheet 111	ISOMETRIC DRAWING LINE		<div>INSULATION CODE / THK. (mm)</div> <div>N 0</div>		<div>ANNEX</div> <div>19</div>		<div>SPEC.</div> <div>L</div>		<div>DRAWING NUMBER</div> <div>19-000-2-02-00001 sheet 2121IW91N28-1</div>		<div>REV.</div> <div>01</div>		
00	ISSUED FOR REFERENCE		09-JUN-23	U.CHAVAN	P.VAZE	G.PAGANONI	LINE LIST N° 19-L-19-000-2-00-80602	1"-IW-91N28-B-1												
REV.	DESCRIPTION		DATE	DRW. BY	CHECK BY	APPR. BY	APPR. CLIENT	PIPE LAYOUT N° 19-L-19-000-2-00-86197 sheet 5												