


THIS DOCUMENT BELONGS TO REPSOL. IT CAN NOT BE COPIED, REPRODUCED AND/OR USED WITHOUT PREVIOUS AUTHORIZATION OF REPSOL. COMPUTERIZED DRAWING (HANDWRITING STRICTLY FORBIDDEN).

EXTR. DATE: 21-10-2023 08:39:29

STREAM NO.: 3250




REV. CAUSE ID:



REMARKS FOR MECHANICAL SUBCONTRACTOR:

- 1) LINES 1.1/2" AND SMALLER SHALL BE SUPPORTED IN FIELD IF NOT OTHERWISE INDICATED.
2) ALL DIMENSION AND PROPER CONFIGURATION FOR LINES NPS 1.1/2" AND SMALLER SHALL BE CHECKED IN FIELD BEFORE CONSTRUCTION.
3) FOR THE COMPONENTS MARKED AS FIELD WELDED WITH THIS SYMBOL , ONE WELD FOR ADJUSTMENT OF IN LINE COMPONENT MUST BE LEFT
4) FOR EXTRA PIPE LENGTH REFER TO 4274-LZ-PC-00000603.
5) GUSSETING TO BE IMPLEMENTED BY MECHANICAL SUBCONTRACTOR AS PER 45-L-45-000-2-00-80004 / 4274-XH-SG-00000002.
6) CROSSING BETWEEN WELDS ON PIPELINE SHALL NOT BE ADMITTED.
7) IN CASE OF DISCREPANCIES BETWEEN DATA SHOWN ON ISO AND IN LINE LIST (AS APPLICABLE, DATA SHOWN IN LINE LIST GOVERN.
8) ACTUAL CUT LENGTH OF PIPE AND FIELD WELDS SHALL BE DEFINED BY MECHANICAL SUBCONTRACTOR (REF.TO 4274-LZ-PC-00000603).
9) WHERE EARTHING BONDING IS REQUIRED, MECHANICAL SUBCONTRACTOR TO PERFORM IT BASED ON DOC. 45-P-000-7-06-00902/ 4274 -NN-DW-00000002 AND ASSEMBLY NO FEA005 AND FE019.

SUPPORTS LEGEND:

 DENOTES PARTS LIST NO
 PIPE SUPPORT
 A=RESTING SUPPORT
 G=GUIDE
 F=AXIAL STOP
 B=ANCHOR
 M=SPRING
 S=TEFLON PAD
WHERE  WITHOUT NUMBERING IS INDICATED, THIS MEANS THAT THERE IS A REST DIRECTLY ON STEEL STRUCTURE.

							STRESS CALC. N° -
							P & ID 19-A-19-000-1-01-00001 sheet 106
00	ISSUED FOR CONSTRUCTION	20-OCT-23	M.YADAV	P.VAZE	G.PAGANONI		LINE LIST N° 19-L-19-000-2-00-80602
REV.	DESCRIPTION	DATE	DRW. BY	CHECK BY	APPR. BY	APPR. CLIENT	PIPE LAYOUT N° 19-L-19-000-2-00-86197 sheet 1

APPROVED FOR
CONSTRUCTION

Signature for construction is shown
on Iso list of relevant CWA

ISOMETRIC DRAWING
LINE

2"-IA-91F62-6C4

BILL OF MATERIAL

PT NO	COMPONENT DESCRIPTION	N.S. (IN)	ITEM CODE	QTY	HOLD STATUS
PIPE					
1	PIPE - A312-TP304/304L DUAL GR BE SMLS T01AL2CV02 S-10S <PIPB04DB2210S> (L-PIP113)	2	13364302	2.3 M	
FITTINGS					
2	STRAIGHT TEE ASME B16.9 A403-WP304/304L DG BE SMLS C31DL2FV01 S-10S <TEBB23DF314071407> (L-TEB28)	2X2	12259149	1	
3	REDUCING SOCKOLET MSS-SP-97 3000# A182-F304/304L DUAL GR BE SWE - R13DNL2AV101 NREQD <SOKB450LB01411> (L-SOK04)	2X3/4	12258338	1	
4	ECCENTRIC SWAGE MSS SP-95 - A403-WP304/304L DG BE PE SMLS SCH1-10S SCH2-40S R22FQL2FVZ10 <ESWB04DGR14071101> (L-ESW20)	2X3/4	12495783	1	
5	90 LR ELBOW ASME B16.9 A403-WP304/304L DG BE SMLS C01DL2FV01 S-10S <90LB23DF3210S> (L-8052)	2	12259133	1	
FLANGES					
6	WN FLANGE ASME B16.5 150# A182-F304/304L DUAL GR RF BE 125 - 250 AARH F01CDL2ABV05 S-10S <WNFB450R15210S> (L-WNF55)	2	12260686	2	
PIPE SUPPORTS					
7	VERTICAL STAKES WELDED TO STR. ST42 L80X80X10	2	375	1	
8	SUPPORT HOR.NOT INS.PIP.N4G1	2	375	1	
GASKETS					
9	SPIRAL WOUND GASKET ASME B16.20 150# RFTBE 304/GRAFOIL SS 304 SS 304 ASME B16.5 G03GDP1IS04 <N/A> (N/A)	2	11654490	1	
BOLTS					
10	STUD BOLTS&NUTS ASME B18.31.2/ B18.2.2 A193-B8M CL2/A194-8MA INCH SIZE I01OB1601 <SB2R58G5/831/2> - 2 NUTS PER BOLT - 85 mm Length	5/8	153458376	4	

PIPE MATERIAL

304, dual grade

HEAT TREATMENT (PWHIT)

N

PAINTING SCHEME (3)

NR

PIPING CLASS

6C4

WELDING CLASS (4)

M

PED CATEGORY

Art 4.3

INSULATION CODE / THK. (mm)

N

0

- NOTES: 1. FOR TECHNICAL DETAILS SEE LINE LIST.
2. FOR VENT, DRAIN OR INSTRUMENT CONNECTION DETAILS SEE 45-L-45-000-2-00-80102.
3. WELDING ACCORDING TO 45-L-45-000-2-00-80021.
4. PAINTING ACCORDING TO 45-A-45-000-1-00-20160.
5. CODE SHOWN IN BOM BETWEEN "<" & ">" DENOTES REPSOL UNICODE. "~N/A~" MEANS UNICODE IS "NOT AVAILABLE".



LOW LINEAL DENSITY POLYETHYLENE (PEL) AND POLYPROPYLENE (PP) PLANTS
FOR PROJECT - ALBA PROJECT

ANNEX
19

SPEC.
L

DRAWING NUMBER
19-000-2-02-00001 sheet 2121IA91F62-6

REV.
00