


THIS DOCUMENT BELONGS TO REPSOL. IT CAN NOT BE COPIED, REPRODUCED AND/OR USED WITHOUT PREVIOUS AUTHORIZATION OF REPSOL. COMPUTERIZED DRAWING (HANDWRITING STRICTLY FORBIDDEN).

EXTR. DATE: 22-07-2023 07:51:06

STREAM NO.: 3202

REV. CAUSE ID:



REMARKS FOR MECHANICAL SUBCONTRACTOR:

- 1) LINES 1.1/2" AND SMALLER SHALL BE SUPPORTED IN FIELD IF NOT OTHERWISE INDICATED.
2) ALL DIMENSION AND PROPER CONFIGURATION FOR LINES NPS 1.1/2" AND SMALLER SHALL BE CHECKED IN FIELD BEFORE CONSTRUCTION.
3) FOR THE COMPONENTS MARKED AS FIELD WELDED WITH THIS SYMBOL ✕ , ONE WELD FOR ADJUSTMENT OF IN LINE COMPONENT MUST BE LEFT
4) FOR EXTRA PIPE LENGTH REFER TO 4274-LZ-PC-00000603.
5) GUSSETING TO BE IMPLEMENTED BY MECHANICAL SUBCONTRACTOR AS PER 45-L-45-000-2-00-80004 / 4274-XH-SG-00000002.
6) CROSSING BETWEEN WELDS ON PIPELINE SHALL NOT BE ADMITTED.
7) IN CASE OF DISCREPANCIES BETWEEN DATA SHOWN ON ISO AND IN LINE LIST (AS APPLICABLE, DATA SHOWN IN LINE LIST GOVERN.
8) ACTUAL CUT LENGTH OF PIPE AND FIELD WELDS SHALL BE DEFINED BY MECHANICAL SUBCONTRACTOR (REF.TO 4274-LZ-PC-00000603).
9) WHERE EARTHING BONDING IS REQUIRED, MECHANICAL SUBCONTRACTOR TO PERFORM IT BASED ON DOC. 45-P-000-7-06-00902/ 4274 -NN-DW-00000002 AND ASSEMBLY NO FEA005 AND FE019.

SUPPORTS LEGEND: [] DENOTES PARTS LIST NO PIPE SUPPORT A=RESTING SUPPORT G=GUIDE F=AXIAL STOP B=ANCHOR M=SPRING S=TEFLON PAD WHERE [] WITHOUT NUMBERING IS INDICATED, THIS MEANS THAT THERE IS A REST DIRECTLY ON STEEL STRUCTURE.

							STRESS CALC. N°
							-
							P & ID
							19-A-19-000-1-01-00001 sheet 114
							LINE LIST N°
00	ISSUED FOR REFERENCE	21-JUL-23	U.CHAVAN	P.VAZE	G.PAGANONI		19-L-19-000-2-00-80602
							PIPE LAYOUT N°
REV.	DESCRIPTION	DATE	DRW. BY	CHECK BY	APPR. BY	APPR. CLIENT	19-L-19-000-2-00-86197 sheet 6

ISSUED FOR REFERENCE



Signature for construction is shown on Iso list of relevant CWA

ISOMETRIC DRAWING LINE

3/4"-HPN-91R02-1E21

BILL OF MATERIAL

PT NO	COMPONENT DESCRIPTION	N.S. (IN)	ITEM CODE	QTY	HOLD STATUS
PIPE					
1	PIPE - A106-B PE SMLS T01AC03Z02 S-XS <PIPA010A13/4XS> (L-6679)	3/4	1132785	0.2 M	
2	PIPE - A106-B PE SMLS T01AC03Z02 S-XS <PIPA010A11/2XS> (L-6679)	1/2	1132777	3.3 M	
FITTINGS					
3	ECCENTRIC SWAGE MSS SP-95 - A105N PE PE SMLS SCH1-XS SCH2-XS R22FQC44ZZ01 <ESWA010AR11161016> (L-ESW31)	3/4X1/2	163782592	1	
4	COUPLING ASME B16.11 3000# A105N SWE SWE - R01FNC441101 NREQD <FCPA300LBK3/4> (L-180)	3/4	11651676	1	
5	TEE ASME B16.11 3000# A105N SWE SWE - R11FNC441101 NREQD <TESA300LBK1/2> (L-179)	1/2X1/2	11651299	2	
6	90 ELBOW ASME B16.11 3000# A105N SWE SWE - R31FNC441103 NREQD <90FA300LBK1/2> (L-178)	1/2	11651295	1	
7	PLUG ROUND HEAD ASME B16.11 - A105N MTE NREQD - R42FQC44W001 NREQD <PLUA300CK1/2> (L-77)	1/2	110088243	1	
FLANGES					
8	SW FLANGE ASME B16.5 600# A105N RFFE SWE 125 - 250 AARH F02CHC44B105 S-XS <SWFA3004651/2XS> (L-376)	1/2	19805863	1	
9	SW FLANGE ASME B16.5 300# A105N RFFE SWE 125 - 250 AARH F02CFC44B105 S-XS <SWFA300R351/2XS> (L-375)	1/2	19762189	1	
VALVES / IN-LINE ITEMS					
10	GATE VALVE API 602 800# A105N SWE SWE 8-F6&HF WB-OS&Y SOW API 602 HW V01GIC4411BL NREQD <G63_4L-GA1313-B> (L-GA1313-B)	3/4	110015418	1	
11	GATE VALVE API 602 800# A105N SWE FTE 8-F6&HF WB-OS&Y SOW API 602 HW V01GIC4412BL NREQD <N/A> (N/A)	1/2	110015409	1	
12	GATE VALVE API 602 800# A105N SWE SWE 8-F6&HF WB-OS&Y SOW API 602 HW V01GIC4411BL NREQD <G61_2L-GA1313-B> (L-GA1313-B)	1/2	110015417	1	
INSTRUMENTS					
13	INSTRUMENT COMPONENT	3/4	19-PI-4013	1	

PIPE MATERIAL		NOTES: 1. FOR TECHNICAL DETAILS SEE LINE LIST. 2. FOR VENT, DRAIN OR INSTRUMENT CONNECTION DETAILS SEE 45-L-45-000-2-00-80102. 3. WELDING ACCORDING TO 45-L-45-000-2-00-80021. 4. PAINTING ACCORDING TO 45-A-45-000-1-00-20160. 5. CODE SHOWN IN BOM BETWEEN "<" & ">" DENOTES REPSOL UNICODE. "~N/A~" MEANS UNICODE IS "NOT AVAILABLE".			
CS					
HEAT TREATMENT (PWHT)					
N					
PAINTING SCHEME (3)		CONTRACTOR: 	CONTRACTOR DRAWING NUMBER: 4274-XH-DL-2121HPN91R02-4	PROJECT: 4001008	
1					
PIPING CLASS					
1E21					
WELDING CLASS (4)		<div><div>LOW LINEAL DENSITY POLYETHYLENE (PEL) AND POLYPROPYLENE (PP) PLANTS FOR PROJECT - ALBA PROJECT</div></div> <div>CLIENT / COMPLEX REPSOL POLYMEROS/ SINES INDUSTRIAL COMPLEX</div>			
E					
PED CATEGORY					
Art 4.3					
INSULATION CODE / THK. (mm)		ANNEX 19	SPEC. L	DRAWING NUMBER 19-000-2-02-00001 sheet 2121HPN91R02-4	REV. 00
N 0					