


THIS DOCUMENT BELONGS TO REPSOL. IT CAN NOT BE COPIED, REPRODUCED AND/OR USED WITHOUT PREVIOUS AUTHORIZATION OF REPSOL. COMPUTERIZED DRAWING (HANDWRITING STRICTLY FORBIDDEN).

EXTR. DATE: 15-06-2023 13:00:40

STREAM NO.: 3200

REV. CAUSE ID: 9



REMARKS FOR MECHANICAL SUBCONTRACTOR:

- 1) LINES 1.1/2" AND SMALLER SHALL BE SUPPORTED IN FIELD IF NOT OTHERWISE INDICATED.
2) ALL DIMENSION AND PROPER CONFIGURATION FOR LINES NPS 1.1/2" AND SMALLER SHALL BE CHECKED IN FIELD BEFORE CONSTRUCTION.
3) FOR THE COMPONENTS MARKED AS FIELD WELDED WITH THIS SYMBOL ✕ , ONE WELD FOR ADJUSTMENT OF IN LINE COMPONENT MUST BE LEFT
4) FOR EXTRA PIPE LENGTH REFER TO 4274-LZ-PC-00000603.
5) GUSSETING TO BE IMPLEMENTED BY MECHANICAL SUBCONTRACTOR AS PER 45-L-45-000-2-00-80004 / 4274-XH-SG-00000002.
6) CROSSING BETWEEN WELDS ON PIPELINE SHALL NOT BE ADMITTED.
7) IN CASE OF DISCREPANCIES BETWEEN DATA SHOWN ON ISO AND IN LINE LIST (AS APPLICABLE, DATA SHOWN IN LINE LIST GOVERN.
8) ACTUAL CUT LENGTH OF PIPE AND FIELD WELDS SHALL BE DEFINED BY MECHANICAL SUBCONTRACTOR (REF.TO 4274-LZ-PC-00000603).
9) WHERE EARTHING BONDING IS REQUIRED, MECHANICAL SUBCONTRACTOR TO PERFORM IT BASED ON DOC. 45-P-000-7-06-00902/ 4274 -NN-DW-00000002 AND ASSEMBLY NO FEA005 AND FE019.

SUPPORTS LEGEND: [] DENOTES PARTS LIST NO PIPE SUPPORT — A=RESTING SUPPORT G=GUIDE F=AXIAL STOP B=ANCHOR M=SPRING S=TEFLON PAD WHERE [] WITHOUT NUMBERING IS INDICATED, THIS MEANS THAT THERE IS A REST DIRECTLY ON STEEL STRUCTURE.

| | | | | | | |
|------|----------------------|-----------|----------|----------|------------|--|
| | | | | | | STRESS CALC. N° |
| | | | | | | - |
| | | | | | | P & ID 19-A-19-000-1-01-00001 sheet 110 |
| 00 | ISSUED FOR REFERENCE | 16-JUN-23 | U.CHAVAN | P.VAZE | G.PAGANONI | LINE LIST N° 19-L-19-000-2-00-80602 |
| REV. | DESCRIPTION | DATE | DRW. BY | CHECK BY | APPR. BY | APPR. CLIENT 19-L-19-000-2-00-86197 sheet 2 |

ISSUED FOR REFERENCE



Signature for construction is shown on Iso list of relevant CWA

ISOMETRIC DRAWING LINE

1"-N-91M58-1C13

BILL OF MATERIAL

| PT NO | COMPONENT DESCRIPTION | N.S. (IN) | ITEM CODE | QTY | HOLD STATUS |
|------------------------|--|-----------|----------------|-------|-------------|
| PIPE | | | | | |
| 1 | PIPE - A106-B PE SMLS T01AC03Z02 S-XS <PIPA010A13/4XS> (L-6679) | 3/4 | I132785 | 1.5 M | |
| FITTINGS | | | | | |
| 2 | CONCENTRIC SWAGE MSS SP-95 - A105N PE PE SMLS SCH1-XS SCH2-XS R21FQC44ZZ01 <CSWA010AR12161116> (L-7890) | 1X3/4 | I63782569 | 1 | |
| 3 | COUPLING ASME B16.11 3000# A105N SWE SWE - R01FNC441101 NREQD <FCPA300LBK1> (L-180) | 1 | I1651677 | 1 | |
| 4 | NIPPLE - - A106-B PE MTE SMLS LENGTH 100mm R03AQC03ZW04 S-XS <NTOA010E1121624> (L-7888) | 1 | I2221194 | 1 | |
| 5 | SPECIALTY COMPONENT | 1 | SP-04-291M0-43 | 1 | |
| 6 | TEE ASME B16.11 3000# A105N SWE SWE - R11FNC441101 NREQD <TESA300LBK3/4> (L-179) | 3/4X3/4 | I1651300 | 1 | |
| 7 | 45 ELBOW ASME B16.11 3000# A105N SWE SWE - R32FNC441101 NREQD <45FA300LBK3/4> (L-184) | 3/4 | I1651294 | 2 | |
| FLANGES | | | | | |
| 8 | SW FLANGE ASME B16.5 150# A105N RFFE SWE 125 - 250 AARH F02CDC44B105 S-XS <SWFA300R153/4XS> (L-295) | 3/4 | I5378342 | 3 | |
| 9 | BLIND FLANGE ASME B16.5 150# A105N RFFE NREQD 125 - 250 AARH F10CDC44B005 <BLFA300R153/4> (L-140) | 3/4 | I1652356 | 1 | |
| GASKETS | | | | | |
| 10 | SPIRAL WOUND GASKET ASME B16.20 150# RFFE 304/PTFE CARBON STEEL SS 304 ASME B16.5 G03GDB11G12 <SPAQ505R1EA3/4> (L-SPA04) | 3/4 | I2230475 | 4 | |
| BOLTS | | | | | |
| 11 | STUD BOLTS&NUTS ASME B18.31.2/ B18.2.2 A193-B7/A194-2H INCH SIZE I01OB0301 <SB2R51G1/221/2> - 2 NUTS PER BOLT - 65 mm Length | 1/2 | I53437190 | 16 | |
| VALVES / IN-LINE ITEMS | | | | | |
| 12 | BALL VALVE API 608 150# A216-WCB RFFE 316/R-PTFE, GF B7/2H 125 - 250 AARH 2PSB-FULL BORE FLOATING BALL OHW ASME B16.5 V04JDC29BZZG NREQD <N/A> (N/A) | 3/4 | I10013686 | 2 | |

| | | | | | |
|-----------------------------|--|---|--|---|-------------------------------|
| PIPE MATERIAL | | <div>NOTES: 1. FOR TECHNICAL DETAILS SEE LINE LIST.</div> <div>2. FOR VENT, DRAIN OR INSTRUMENT CONNECTION DETAILS SEE 45-L-45-000-2-00-80102.</div> <div>3. WELDING ACCORDING TO 45-L-45-000-2-00-80021.</div> <div>4. PAINTING ACCORDING TO 45-A-45-000-1-00-20160.</div> <div>5. CODE SHOWN IN BOM BETWEEN "<" & ">" DENOTES REPSOL UNICODE. "<N/A>" MEANS UNICODE IS "NOT AVAILABLE".</div> | | | |
| CS | | | | | |
| HEAT TREATMENT (PWHT) | | | | | |
| N | | | | | |
| PAINTING SCHEME (3) | | <div>CONTRACTOR:</div> <div></div> | <div>CONTRACTOR DRAWING NUMBER:</div> <div>4274-XH-DL-2121N91M58-3</div> | <div>PROJECT:</div> <div>4001008</div> | |
| 1 | | | | | |
| PIPING CLASS | | <div><div>LOW LINEAL DENSITY POLYETHYLENE (PEL) AND POLYPROPYLENE (PP) PLANTS FOR PROJECT - ALBA PROJECT</div><div>CLIENT / COMPLEX REPSOL POLYMEROS/ SINES INDUSTRIAL COMPLEX</div></div> | | | |
| IC13 | | | | | |
| WELDING CLASS (4) | | | | | |
| E | | | | | |
| PED CATEGORY | | | | | |
| Art 4.3 | | | | | |
| INSULATION CODE / THK. (mm) | | <div>ANNEX</div> <div>19</div> | <div>SPEC.</div> <div>L</div> | <div>DRAWING NUMBER</div> <div>19-000-2-02-00001 sheet 2121N91M58-3</div> | <div>REV.</div> <div>00</div> |
| N 0 | | | | | |