


THIS DOCUMENT BELONGS TO REPSOL. IT CAN NOT BE COPIED, REPRODUCED AND/OR USED WITHOUT
PREVIOUS AUTHORIZATION OF REPSOL. COMPUTERIZED DRAWING (HANDWRITING STRICTLY FORBIDDEN).

EXTR. DATE: 14-03-2024 16:27:56

STREAM NO.:4527

REV. CAUSE ID: 2



REMARKS FOR MECHANICAL SUBCONTRACTOR:

- 1) LINES 1.1/2" AND SMALLER SHALL BE SUPPORTED IN FIELD IF NOT OTHERWISE INDICATED.
2) ALL DIMENSION AND PROPER CONFIGURATION FOR LINES NPS 1.1/2" AND SMALLER SHALL BE CHECKED IN FIELD BEFORE CONSTRUCTION.
3) FOR THE COMPONENTS MARKED AS FIELD WELDED WITH THIS SYMBOL , ONE WELD FOR ADJUSTMENT OF IN LINE COMPONENT MUST BE LEFT
4) FOR EXTRA PIPE LENGTH REFER TO 4274-LZ-PC-00000603.
5) GUSSETING TO BE IMPLEMENTED BY MECHANICAL SUBCONTRACTOR AS PER 45-L-45-000-2-00-80004 / 4274-XH-SG-00000002.
6) CROSSING BETWEEN WELDS ON PIPELINE SHALL NOT BE ADMITTED.
7) IN CASE OF DISCREPANCIES BETWEEN DATA SHOWN ON ISO AND IN LINE LIST (AS APPLICABLE, DATA SHOWN IN LINE LIST GOVERN.
8) ACTUAL CUT LENGTH OF PIPE AND FIELD WELDS SHALL BE DEFINED BY MECHANICAL SUBCONTRACTOR (REF.TO 4274-LZ-PC-00000603).
9) WHERE EARTHING BONDING IS REQUIRED, MECHANICAL SUBCONTRACTOR TO PERFORM IT BASED ON DOC. 45-P-000-7-06-00902/ 4274 -NN-DW-00000002 AND ASSEMBLY NO FE005 AND FE019.

SUPPORTS LEGEND:  DENOTES PARTS LIST NO  PIPE SUPPORT  A=RESTING SUPPORT G=GUIDE F=AXIAL STOP B=ANCHOR M=SPRING S=TEFLON PAD WHERE  WITHOUT NUMBERING IS INDICATED, THIS MEANS THAT THERE IS A REST DIRECTLY ON STEEL STRUCTURE.

							STRESS CALC. N° -
01	ISSUED FOR REFERENCE	14-MAR-24	M.YADAV	P.VAZE	G.PAGANONI		P & ID 19-A-19-000-1-01-00001 sheet 43
00	ISSUED FOR REFERENCE	06-OCT-23	M.YADAV	P.VAZE	G.PAGANONI		LINE LIST N° 19-L-19-000-2-00-80602
REV.	DESCRIPTION	DATE	DRW. BY	CHECK BY	APPR. BY	APPR. CLIENT	PIPE LAYOUT N° 19-L-19-000-2-00-86197 sheet 4

ISSUED FOR
REFERENCE

Signature for construction is shown
on Iso list of relevant CWA

TITLE
ISOMETRIC DRAWING
LINE

1/2"-SCT-40M12-6G69 (ET)

BILL OF MATERIAL

PT NO	COMPONENT DESCRIPTION	N.S. (IN)	ITEM CODE	QTY	HOLD STATUS
PIPE					
1	TUBE - A269-TP316/316L-DUAL GRADE PE SMLS T02ALK7Z01 0.065" tubing <N/A> (N/A)	1/2	17062245	3.1 M	
FITTINGS					
2	COMPR UNION TEE MFTR - A182-F316/316L DUAL GR FFRE FFRE - R64AQL1M7708 NREQD <N/A> (N/A)	1/2X1/2	17062366	1	
3	45 LATERAL ASME B16.11/AA 6000# A182-F316/316L DUAL GR FTE FTE - R17ROL1M2201 Undefined <N/A> (N/A)	1/2X1/2	163151575	1	
4	COMPR MALE CONNECT MFTR - A182-F316/316L DUAL GR FFRE MTE - R60AQL1M7W10 NREQD <N/A> (N/A)	1/2	145425129	2	
5	COMPR MALE CONNECT MFTR - A182-F316/316L DUAL GR PE PE PORT CONNECTOR (SS-811-PC) OR EQUIVALENT R60AQL1MZZ26 NREQD <N/A> (N/A)	1/2	167355609	1	
6	SPECIALTY COMPONENT	1/2	19-FX-4007	1	
VALVES / IN-LINE ITEMS					
7	COMPR BALL VALVE MFTR 6000# A182-F316/316L DUAL GR FFRE FFRE 316-CARBON/GLASS REINFORCED PTFE TRUNNION-MOUNTED OHW V70AOL1M7739 NREQD <N/A> (N/A)	1/2	165625050	2	

PIPE MATERIAL

316, dual grade

HEAT TREATMENT (P/WHIT)

-

PAINTING SCHEME (3)

NR

PIPING CLASS

6G69

WELDING CLASS (4)

-

PED CATEGORY

Art 4.3

INSULATION CODE / THK. (mm)

ET 30

NOTES: 1. FOR TECHNICAL DETAILS SEE LINE LIST.

2. FOR VENT, DRAIN OR INSTRUMENT CONNECTION DETAILS SEE 45-L-45-000-2-00-800102.
3. WELDING ACCORDING TO 45-L-45-000-2-00-80021.
4. PAINTING ACCORDING TO 45-A-45-000-1-00-20160.
5. CODE SHOWN IN BOM BETWEEN "<" & ">" DENOTES REPSOL UNICODE. "<N/A>" MEANS UNICODE IS "NOT AVAILABLE".



LOW LINEAL DENSITY POLYETHYLENE (PEL) AND POLYPROPYLENE (PP) PLANTS FOR PROJECT - ALBA PROJECT

CLIENT / COMPLEX
REPSOL POLYMEROS/
SINES INDUSTRIAL COMPLEX

ANNEX
19

SPEC.
L

DRAWING NUMBER
19-000-2-02-00001 sheet 2121SCT40M12-2

REV.
01