


THIS DOCUMENT BELONGS TO REPSOL. IT CAN NOT BE COPIED, REPRODUCED AND/OR USED WITHOUT PREVIOUS AUTHORIZATION OF REPSOL. COMPUTERIZED DRAWING (HANDWRITING STRICTLY FORBIDDEN).

EXTR. DATE: 25-01-2023 13:27:15


STREAM NO.:4921


REV. CAUSE ID:



BILL OF MATERIAL					
PT NO	COMPONENT DESCRIPTION	N.S. (IN)	ITEM CODE	QTY	HOLD STATUS
PIPE					
1	PIPE - A106-B PE SMLS T01AC03Z02 S-XS <PIPA010A11/2XS> (L-6679)	1/2	I132777	0.2 M	
FITTINGS					
2	DRIP RING YH-ST-D08 300# A516-70 NORM. FFTBE 125 - 250 AARH SUPPL. REQ. S5 ASME B16.5 D0108FC65O02 NREQD <N/A> (N/A).	3	I5407995	1	
FLANGES					
3	SW FLANGE ASME B16.5 150# A105N RFFE SWE 125 - 250 AARH F02CDC44B105 S-XS <SWFA300R151/2XS> (L-295)	1/2	I5378341	2	
4	BLIND FLANGE ASME B16.5 150# A105N RFFE NREQD 125 - 250 AARH F10CDC44B005 <BLFA300R151/2> (L-140)	1/2	I1652355	2	
GASKETS					
5	SPIRAL WOUND GASKET ASME B16.20 300# RFTBE 304/GRAFOIL CARBON STEEL SS 304 ASME B16.5 G03GFP1IS12 <N/A> (N/A)	3	I63508968	3	
6	SPIRAL WOUND GASKET ASME B16.20 150# RFTBE 304/GRAFOIL CARBON STEEL SS 304 ASME B16.5 G03GDP1IS12 <N/A> (N/A)	1/2	I63508894	4	
BOLTS					
7	STUD BOLTS&NUTS ASME B18.31.2/ B18.2.2 A193-B7/A194-2H INCH SIZE I01OB0301 <SB2R51G3/441/4> - 2 NUTS PER BOLT - 110 mm Length	3/4	I53437465	8	
8	STUD BOLTS&NUTS ASME B18.31.2/ B18.2.2 A193-B7/A194-2H INCH SIZE I01OB0301 <SB2R51G3/461/4> - 2 NUTS PER BOLT - 160 mm Length	3/4	I53437475	8	
9	STUD BOLTS&NUTS ASME B18.31.2/ B18.2.2 A193-B7/A194-2H INCH SIZE I01OB0301 <SB2R51G1/221/2> - 2 NUTS PER BOLT - 60 mm Length	1/2	I53437179	16	
VALVES / IN-LINE ITEMS					
10	BALL VALVE API 608 300# A216-WCB RFFE 316/R-PTFE, GF B7/2H 125 - 250 AARH 2PSB-FULL BORE FLOATING BALL LE ASME B16.5 V04JFC29BTR NREQD <B43L-AL083> (L-AL083).	3	I9764127	1	
11	BALL VALVE API 608 150# A216-WCB RFFE 316/R-PTFE, GF B7/2H 125 - 250 AARH 2PSB-FULL BORE FLOATING BALL OHW ASME B16.5 V04JDC29BZZG NREQD <N/A> (N/A)	1/2	I10013685	2	
INSTRUMENTS					
12	INSTRUMENT COMPONENT	3	I9-PT-4015	1	

REMARKS FOR MECHANICAL SUBCONTRACTOR:

- 1) LINES 1.1/2" AND SMALLER SHALL BE SUPPORTED IN FIELD IF NOT OTHERWISE INDICATED.
2) ALL DIMENSION AND PROPER CONFIGURATION FOR LINES NPS 1.1/2" AND SMALLER SHALL BE CHECKED IN FIELD BEFORE CONSTRUCTION.
3) FOR THE COMPONENTS MARKED AS FIELD WELDED WITH THIS SYMBOL , ONE WELD FOR ADJUSTMENT OF IN LINE COMPONENT MUST BE LEFT
4) FOR EXTRA PIPE LENGTH REFER TO 4274-LZ-PC-00000603.
5) GUSSETING TO BE IMPLEMENTED BY MECHANICAL SUBCONTRACTOR AS PER 45-L-45-000-2-00-80004 / 4274-XH-SG-00000002.
6) CROSSING BETWEEN WELDS ON PIPELINE SHALL NOT BE ADMITTED.
7) IN CASE OF DISCREPANCIES BETWEEN DATA SHOWN ON ISO AND IN LINE LIST (AS APPLICABLE, DATA SHOWN IN LINE LIST GOVERN.
8) ACTUAL CUT LENGTH OF PIPE AND FIELD WELDS SHALL BE DEFINED BY MECHANICAL SUBCONTRACTOR (REF.TO 4274-LZ-PC-00000603).
9) WHERE EARTHING BONDING IS REQUIRED, MECHANICAL SUBCONTRACTOR TO PERFORM IT BASED ON DOC. 45-P-000-7-06-00902/ 4274 -NN-DW-00000002 AND ASSEMBLY NO FEA005 AND FE019.

SUPPORTS LEGEND:		PIPE SUPPORT	A=RESTING SUPPORT WHERE  WITHOUT NUMBERING IS INDICATED, THIS MEANS THAT THERE IS A REST DIRECTLY ON STEEL STRUCTURE.	G=GUIDE	F=AXIAL STOP	B=ANCHOR	M=SPRING	S=TEFLON PAD
------------------	--	--------------	--	---------	--------------	----------	----------	--------------



							STRESS CALC. N°
							-
							P & ID
							19-A-19-000-1-01-00001 sheet 51
00	ISSUED FOR CONSTRUCTION	27-JAN-23	U.CHAVAN	P.VAZE	G.PAGANONI		LINE LIST N°
							19-L-19-000-2-00-80602
REV.	DESCRIPTION	DATE	DRW. BY	CHECK BY	APPR. BY	APPR. CLIENT	PIPE LAYOUT N°
							19-L-19-000-2-00-86197 sheet 3

APPROVED FOR CONSTRUCTION

Signature for construction is shown on Iso list of relevant CWA

ISOMETRIC DRAWING LINE

3"-VZ-40Z02-1C17 (ET)

PIPE MATERIAL		NOTES: 1. FOR TECHNICAL DETAILS SEE LINE LIST. 2. FOR VENT, DRAIN OR INSTRUMENT CONNECTION DETAILS SEE 45-L-45-000-2-00-80102. 3. WELDING ACCORDING TO 45-L-45-000-2-00-80021. 4. PAINTING ACCORDING TO 45-A-45-000-1-00-20160. 5. CODE SHOWN IN BOM BETWEEN "<" & ">" DENOTES REPSOL UNICODE. "<N/A>" MEANS UNICODE IS "NOT AVAILABLE".				
CS						
HEAT TREATMENT (PWHT)						
N						
PAINTING SCHEME (3)			CONTRACTOR:		CONTRACTOR DRAWING NUMBER:	PROJECT:
20					4274-XH-DL-2121VZ40Z02-1	4001008
PIPING CLASS						
1C17						
WELDING CLASS (4)		 <div>LOW LINEAL DENSITY POLYETHYLENE (PEL) AND POLYPROPYLENE (PP) PLANTS FOR PROJECT - ALBA PROJECT</div>				CLIENT / COMPLEX REPSOL POLYMEROS/ SINES INDUSTRIAL COMPLEX
E						
PED CATEGORY						
Art 4.3						
INSULATION CODE / THK. (mm)		ANNEX 19	SPEC. L	DRAWING NUMBER 19-000-2-02-00001 sheet 2121VZ40Z02-1		REV. 00
ET 30						