


THIS DOCUMENT BELONGS TO REPSOL. IT CAN NOT BE COPIED, REPRODUCED AND/OR USED WITHOUT PREVIOUS AUTHORIZATION OF REPSOL. COMPUTERIZED DRAWING (HANDWRITING STRICTLY FORBIDDEN).


EXTR. DATE: 14-09-2023 10:18:03

STREAM NO.:4535

REV. CAUSE ID:



REMARKS FOR MECHANICAL SUBCONTRACTOR:

- 1) LINES 1.1/2" AND SMALLER SHALL BE SUPPORTED IN FIELD IF NOT OTHERWISE INDICATED.
2) ALL DIMENSION AND PROPER CONFIGURATION FOR LINES NPS 1.1/2" AND SMALLER SHALL BE CHECKED IN FIELD BEFORE CONSTRUCTION.
3) FOR THE COMPONENTS MARKED AS FIELD WELDED WITH THIS SYMBOL , ONE WELD FOR ADJUSTMENT OF IN LINE COMPONENT MUST BE LEFT
4) FOR EXTRA PIPE LENGTH REFER TO 4274-LZ-PC-00000603.
5) GUSSETING TO BE IMPLEMENTED BY MECHANICAL SUBCONTRACTOR AS PER 45-L-45-000-2-00-80004 / 4274-XH-SG-00000002.
6) CROSSING BETWEEN WELDS ON PIPELINE SHALL NOT BE ADMITTED.
7) IN CASE OF DISCREPANCIES BETWEEN DATA SHOWN ON ISO AND IN LINE LIST (AS APPLICABLE, DATA SHOWN IN LINE LIST GOVERN.
8) ACTUAL CUT LENGTH OF PIPE AND FIELD WELDS SHALL BE DEFINED BY MECHANICAL SUBCONTRACTOR (REF.TO 4274-LZ-PC-00000603).
9) WHERE EARTHING BONDING IS REQUIRED, MECHANICAL SUBCONTRACTOR TO PERFORM IT BASED ON DOC. 45-P-000-7-06-00902/ 4274 -NN-DW-00000002 AND ASSEMBLY NO FE005 AND FE019.

SUPPORTS LEGEND:  DENOTES PARTS LIST NO PIPE SUPPORT  A=RESTING SUPPORT G=GUIDE F=AXIAL STOP B=ANCHOR M=SPRING S=TEFLON PAD WHERE  WITHOUT NUMBERING IS INDICATED, THIS MEANS THAT THERE IS A REST DIRECTLY ON STEEL STRUCTURE.

| | | | | | | | |
|------|----------------------|-----------|---------|----------|------------|--------------|--|
| | | | | | | | STRESS CALC. N° |
| | | | | | | | - |
| | | | | | | | P & ID 19-A-19-000-1-01-00001 sheet 46 |
| 00 | ISSUED FOR REFERENCE | 15-SEP-23 | M.YADAV | P.VAZE | G.PAGANONI | | LINE LIST N° 19-L-19-000-2-00-80602 |
| REV. | DESCRIPTION | DATE | DRW. BY | CHECK BY | APPR. BY | APPR. CLIENT | PIPE LAYOUT N° 19-L-19-000-2-00-86196 sheet 2 |

ISSUED FOR
REFERENCE



Signature for construction is shown
on Iso list of relevant CWA

TITLE
**ISOMETRIC DRAWING
LINE**

1/2"-LW-40M06-1C17 (ET)

BILL OF MATERIAL

| PT NO | COMPONENT DESCRIPTION | N.S. (IN) | ITEM CODE | QTY | HOLD STATUS |
|------------------------|---|-----------|-----------|-------|-------------|
| PIPE | | | | | |
| 1 | PIPE - A106-B PE SMLS T01AC03Z02 S-XS <PIPA010A11/2XS> (L-6679) | 1/2 | I132777 | 0.8 M | |
| FITTINGS | | | | | |
| 2 | TEE ASME B16.11 3000# A105N SWE SWE - R11FNC441101 NREQD <TESA300LBK1/2> (L-179) | 1/2X1/2 | I1651299 | 1 | |
| 3 | 45 ELBOW ASME B16.11 3000# A105N SWE SWE - R32FNC441101 NREQD <45FA300LBK1/2> (L-184) | 1/2 | I1651291 | 2 | |
| 4 | PLUG ROUND HEAD ASME B16.11 - A105N MTE NREQD - R42FQC44W001 NREQD <PLUA300CK1/2> (L-77) | 1/2 | I10088243 | 1 | |
| FLANGES | | | | | |
| 5 | SW FLANGE ASME B16.5 150# A105N RFFE SWE 125 - 250 AARH F02CDC44B105 S-XS <SWFA300R151/2XS> (L-295) | 1/2 | I5378341 | 2 | |
| GASKETS | | | | | |
| 6 | SPIRAL WOUND GASKET ASME B16.20 150# RFTBE 304/GRAFOIL CARBON STEEL SS 304 ASME B16.5 G03GDP1IS12 <N/A> (N/A) | 1/2 | I63508894 | 2 | |
| BOLTS | | | | | |
| 7 | STUD BOLTS&NUTS ASME B18.31.2/ B18.2.2 A193-B7/A194-2H INCH SIZE I01OB0301 <SB2R51G1/221/2> - 2 NUTS PER BOLT - 60 mm Length | 1/2 | I53437179 | 8 | |
| VALVES / IN-LINE ITEMS | | | | | |
| 8 | BALL VALVE API 608 150# A216-WCB RFFE 316/R-PTFE, GF B7/2H 125 - 250 AARH 2PSB-FULL BORE FLOATING BALL OHW ASME B16.5 V04JDC29BZZG NREQD <N/A> (N/A) | 1/2 | I10013685 | 1 | |
| 9 | BALL VALVE ASME B16.34 800# A105N SWE FTE 316/R-PTFE, GF 3PSB-RED BORE FLOATING BALL OHW FIRE SAFE :API 607 & ANTISTATIC DEVICES "A60T series" TEAL V04JIC44126IG NREQD <N/A> (N/A) | 1/2 | I67130076 | 1 | |

| | | | | |
|-----------------------------|--|--|----------------------------|--|
| PIPE MATERIAL | NOTES: 1. FOR TECHNICAL DETAILS SEE LINE LIST. 2. FOR VENT, DRAIN OR INSTRUMENT CONNECTION DETAILS SEE 45-L-45-000-2-00-80102. 3. WELDING ACCORDING TO 45-L-45-000-2-00-80021. 4. PAINTING ACCORDING TO 45-A-45-000-1-00-20160. 5. CODE SHOWN IN BOM BETWEEN "<" & ">" DENOTES REPSOL UNICODE. "<N/A>" MEANS UNICODE IS "NOT AVAILABLE". | | | |
| CS | | | | |
| HEAT TREATMENT (PWHIT) | | | | |
| N | | | | |
| PAINTING SCHEME (3) | 20 | CONTRACTOR: | CONTRACTOR DRAWING NUMBER: | PROJECT: |
| PIPING CLASS | 1C17 |  | 4274-XH-DL-2121LW40M06-1 | 4001008 |
| WELDING CLASS (4) | E |  LOW LINEAL DENSITY POLYETHYLENE (PEL) AND POLYPROPYLENE (PP) PLANTS FOR PROJECT - ALBA PROJECT | | |
| PED CATEGORY | Art 4.3 | | | |
| INSULATION CODE / THK. (mm) | ET 30 | ANNEX 19 | SPEC. L | DRAWING NUMBER 19-000-2-02-00001 sheet 2121LW40M06-1 |
| | | | | REV. 00 |